

Brief

Reconstruction of Albion Bridge

This project forms part of the emergency works initiated by the Government of Mauritius to alleviate the flooding problems in the village of Albion. The existing structure is of reinforced concrete box culverts with dimensions 2.30m x 6.0m x 0.90m. During heavy rainfall, the culverts are flooded with the increase volume of water from the river, and the road above become inaccessible to the inhabitants. Alternative route onto lateral roads can be used to access on the Albion Road, B78 through the light house. The new bridge will be of dimension 11.0m x 7.0m x 1.60 m.

The scope of works for the above project is as follows:

- Demolition of existing bridge (culverts),
- Construction of a new bridge with footpath,
- Re-profiling of Albion Approach Road, B105 on a stretch of 120m,
- Construction of footpath over a length of 200m,
- Provision of street lighting on the bridge.

Start Date : 10 September 2018

Completion Date : 15 May 2019

Duration : 9 months

Estimated Cost : Rs. 14 M