

Project: FLOOD MITIGATING MEASURES AT ANSE JONCHEE ALONG B28 ROAD

Contract Data

Employer: ROAD DEVELOPMENT AUTHORITY

Contractor: REHM GRINAKER CONSTRUCTION CO. LTD

Contract Sum: Rs183,525.516.90 (Vat Incl)

Letter of Acceptance: 28th December 2022

Commencement of Works: 7th February 2023

Duration: 365 days

Location of Site

The site of Works is located at Anse Jonchee.

Scope of Works

The Works shall consist of the following: -

- 1) Demolition of two existing culverts. Design and Construct of two Reinforced Concrete bridges;
 - One of approximate length 18 m and span 9 m, and
 - One of span 8 m.
 - Both bridges to be of width 11.0 m and having a clear height of minimum 2.5 m
- 2) Horizontal Extension of an existing culvert from a width of 6.5 m to 11.0 m.
- 3) Vertical re-profiling of the road and raising the height of the existing road by an average height of 1.2 m over a length of 550 m.
- 4) Enlargement of the road from 6.5 m to 10 m (2 lanes of 3.5 m wide and shoulders of 1.5 m on both sides of the road) over a length of 550 m
- 5) Construction of Masonry retaining structure for road widening upstream
- 6) Construction of Bus Lay-bys (2 Nos.) and relocation of existing Bus Shelters.
- 7) Modification, protection and relocation of existing services such as telecom (MT), electricity supply (CEB) and water supply (CWA)
- 8) Provision of footpath and road side drains;
- 9) Provide adequate road furniture